## BANKING EQUIPMENT NOTES

KIOSKS

THE ELECTRICAL CONTRACTOR SHALL FURNISH ALL ELECTRICAL SERVICES INCLUDING CONDUITS, JUNCTION BOXES, OUTLETS, WIRES AND HOOK-UP FOR TELLER TERMINAL AND KIOSK LOCATIONS. REFER TO MANUFACTURER'S DRAWINGS PROVIDED BY ARCHITECT FOR EXACT DETAILS AND SPECIFICATIONS.

SOUND SYSTEM AND CONTROL

THE ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL ALL CONDUITS AND PULL ALL CABLE FOR SOUND AND CONTROL WIRING. REFER TO MANUFACTURER'S DRAWINGS PROVIDED BY ARCHITECT FOR EXACT DETAILS AND SPECIFICATIONS.

FUTURE ATM

THE ELECTRICAL CONTRACTOR SHALL FURNISH ALL EMPTY CONDUITS WITH FISH CABLES, JUNCTION BOXES, OUTLETS FOR POWER WIRING AND CONTROL WIRING. REFER TO MANUFACTURER'S DRAWINGS PROVIDED BY ARCHITECT FOR EXACT DETAILS AND SPECIFICATIONS.

## ALARM SYSTEM NOTES

THE ELECTRICAL CONTRACTOR SHALL FURNISH ALL CONDUITS, POWER OUTLETS, OUTLETS, JUNCTION BOXES, ELECTRICAL WIRING, PENETRATORS, SECURITY SYSTEM WIRING, ETC. REFER TO MANUFACTURER'S DRAWINGS PROVIDED BY ARCHITECT FOR EXACT DETAILS AND SPECIFICATIONS.

THIS DRAWING INDICATES ONLY ITEM REQUIRED TO BE RUN BELOW FLOOR. FOR ADDITIONAL EQUIPMENT LOCATIONS AND SPECIFICATIONS REFER TO ALARM SYSTEM LAYOUT DRAWING PROVIDED BY ARCHITECT.

(A) DESK ALARM FLOOR BOX WITH COVER. COORDINATE EXACT LOCATION WITH FURNITURE LAYOUT AND ARCHITECT.

(B) 3/4" CONDUIT BELOW FLOOR.

(C) RUN CONDUIT THRU NEW WALL TO ABOVE CEILING AND CONTINUE TO MAIN SPLICE BOX.

# FLOOR PLAN - POWER

SCALE: 1/4" = 1' - 0"

NOTE:
DO NOT SCALE DRAWING
Each contractor is to verify all existing conditions and all dimensions before beginning any work. Each contractor is to fully coordinate his work with that of others. REFER TO THE CONTRACT AND SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

COMMONWEALTH OF PENNSYLVANIA REGISTERED PROFESSIONAL ENGINEER GEORGE CLIFFORD DeBRUHL 26118-E

| Revisions | By |
|---|---|
| | |

COMMERCIAL DESIGN & DEVELOPMENT, INC.
*Specializing in Planning & Development of Financial Facilities*
3616 Graham Avenue
Windber, Pa. 15963 (814)467-5681

FLOOR PLAN - POWER
NEW BRANCH OFFICE & TRUST OFFICE FOR
MOXHAM NATIONAL BANK
550 CENTRAL AVE., JOHNSTOWN, PA. 15902

| | |
|---|---|
| Printed | |
| Date | 7-7-92 |
| Scale | AS SHOWN |
| Drawn | BJP |
| Job | |
| Sheet | E - 3 |